

ROBERT E. BUSHNELL*†

JOSEPH G. SEEBER°

JOHN C. BROSKY*+

ARREN R. CREW+*

ATHEW J. LESTINA†*

ADVINDER S. SAHOTA†*

RICHARD H. STERN°

MICHAEL D. PARKER

DA. GESELOWITZ, Ph.D.

(REG. PATENT AGENTS)

† ADMITTED IN MARYLAND

° ADMITTED IN VIRGINIA

+ ADMITTED IN PENNSYLVANIA

‡ ADMITTED IN NEW YORK

° ADMITTED IN CONNECTICUT

* NOT ADMITTED IN D.C.

R. E. BUSHNELL

ATTORNEY AT LAW

1522 K STREET, N.W., SUITE 300
WASHINGTON, D.C. 20005-1202
UNITED STATES OF AMERICA

INTELLECTUAL PROPERTY LAW

TELEPHONE (202) 408-9040

FACSIMILE (202) 289-7100

FACSIMILE (202) 628-3835

FACSIMILE (410) 747-0022

E-MAIL: REBUSHNELL@AOL.COM

6 July 2000

☐ U.S. Postal Service

☐ Via Local Courier

☐ Via International Courier

☐ Via Facsimile No. _____

☐ Via E-Mail Attachment

☐ Please Acknowledge Receipt

Assistant Commissioner for Patents
Washington, D.C. 20231

Attorney Docket: P56147

Sir:

Submitted herewith is the following patent application:

Inventor: 1) SU-JONG JUNG

Title: METHOD FOR ENHANCING THE IMAGE QUALITY OF AN
IMAGE FORMING APPARATUS

Please find attached hereto an application for patent which includes: Specification and Abstract,
Claims, original Declaration And Power of Attorney, Assignment, and a certified copy of the
foreign priority document identified below:

Verified Showing of Small Entity Status: **NO**

Drawings: Formal drawings, 5 sheets, Figures 1 through 5

Claim of priority under 35 U.S.C. §119: **YES**

** The Republic Of Korea Application No. 27215/1999 filed on 6 July 1999.

FEE (see formula below): CHECK IS NOT ENCLOSED

Basic Fee \$345/690 **\$690.00**

Additional Fees:

Total number of claims in excess of 20: ____ times \$9/18 . **\$0.00**

Number of independent claims in excess of 3: ____ times \$39/78 **\$0.00**

Multiple Dependent Claims \$130/260 **\$0.00**

An Assignment is likewise enclosed: Recording Fee \$40 . . **\$0.00**

Filing Non-English specification **\$0.00**

TOTAL FEES FOR THE ABOVE APPLICATION **\$690.00**

Assistant Commissioner for Patents

6 July 2000

Page Two

Docket No.: P56147

Inventor: 1) SU-JONG JUNG


Title: METHOD FOR ENHANCING THE IMAGE QUALITY OF AN
IMAGE FORMING APPARATUS

In view of the above, it is requested that this application be accorded a filing date pursuant to 37 CFR 1.53(b).

Please address all correspondence to:

Robert E. Bushnell
1522 K Street, N.W.
Suite 300
Washington, D.C. 20005-1202

Respectfully submitted,



Robert E. Bushnell
(Registration No. 27,774)
Payor No.: 008-439
Attorney for the Applicant
1522 K Street, N.W.
Suite 300
Washington, D.C. 20005-1202

Telephone: (202) 408-9040
Telefacsimile: (202) 628-0755

REB/na

009020 2667950

TITLE

**METHOD FOR ENHANCING THE IMAGE QUALITY OF AN IMAGE
FORMING APPARATUS**

CLAIM OF PRIORITY

This application makes reference to, incorporates the same herein, and claims all benefits accruing under 35 U.S.C. §119 from an application *METHOD FOR ENHANCING THE IMAGE QUALITY OF AN IMAGE FORMING APPARATUS* for earlier filed in the Korean Industrial Property Office on the 6th day of the month of July 1999, and there duly assigned Serial No. 27215/1999.

BACKGROUND OF INVENTION

Field of the Invention

The present invention relates to image formation process and apparatus generally, and, more particularly, to image formation process and apparatus for enhancing the image quality of images printed on thicker, albeit narrower paper while employing an electrophotographic developing technique.

Description of the Related Art

In general, an image forming apparatus that employs an electrophotographic developing technique such as a facsimile, a printer and a complex machine, is equipped with an electrification

1 roller, a photosensitive drum, a transfer roller, a developing roller, a toner supply roller, a fixer and
2 a laser scanning unit (*i.e.*, a "LSU") for printing images onto a printable media such as a cut sheet
3 of paper. I have noticed deficiencies in the pre-transfer system of image forming processes and
4 apparatus. By way of example, if the user intends to form an image on a printable material that is
5 relatively thicker than the standard grade of xerographic paper such as an envelope, the toner coated
6 on the photosensitive drum is not transferred onto the paper and the remaining toner on the
7 photosensitive drum is transferred onto the next piece of printable material that passes along the path
8 conveying the printable material through the apparatus, thereby causing a mis-transfer which is
9 referred to as "ghost development", because the transfer electric field can not transmit the thick
10 paper. Moreover, when a thick envelope having a relatively narrower width in comparison to a sheet
11 of A4 or 8½" by 11" paper is used in a transfer system using a conductive roller, in a state wherein
12 a high voltage required for the transfer is applied to the transfer roller, the conductive layer of the
13 photosensitive drum is broken. This defect is frequently referred to as a "pin hole", and occurs in
14 the region (either on the right, the left, or possibly on both sides of the sheet of the printable media)
15 where the transfer roller and the photosensitive drum come into direct contact with each other due
16 to the absence of any intermediate printable media, thereby causing fatal and unrepairable damage
17 to the photosensitive exterior circumferential surface of drum

18 SUMMARY OF THE INVENTION

19 It is, therefore, a primary object of the present invention to provide an improved image
20 formation process and apparatus.

1 It is another object to provide an image formation process and apparatus demonstrating an
2 enhancement of image quality of the images formed by the process and the apparatus.

3 It is still another object to provide an image formation process and apparatus capable of
4 improving transfer efficiency.

5 It is yet another object to provide an image formation process and apparatus capable of
6 forming a high quality of image on a thicker paper.

7 It is still yet another object to provide an image formation process and apparatus capable of
8 minimizing damage to the photosensitive drum while printing images upon media that have a width
9 less than the axial length of the photosensitive drum.

10 It is a further object to provide an image formation process and apparatus capable of for
11 enhancing the image quality of printed images while preventing damage of the photosensitive drum
12 although a transfer roller directly contacts the photosensitive drum in case an image is formed on
13 a thick envelope with a narrow width.

14 These and other objects may be attained according to the principles of the present invention,
15 with an image formation process and apparatus using either a reduced number of pixels of light
16 emitted from a laser scanning unit, a decreased amount of light or an increased level of developing
17 voltage by faintly treating the image signals generated by a controller.

18 In accordance with one aspect of the present invention, the process contemplates storing
19 image data to be printed at a memory if a print demand is received; detecting the kind of paper
20 selected by a user; editing by reducing the number of pixels of the image data at a certain rate if the
21 detected paper is a thick; and transmitting the edited image data to the LSU and performing the

printing work for the edited image data. The editing step may include equally splitting the pixels of the light scanned into an integer number of pixels in order to represent one pixel of the image data, and editing by using Econo mode at which only a certain number of pixels among the equally split pixels of the light are scanned. In addition, the editing step may include splitting the print area into a plurality of small areas, and editing by using Ret mode at which some pixels among the total pixels for the resolution included in the respective split small areas are removed.

In accordance with another aspect of the present invention, the process contemplates storing image data to be printed at a memory if a print demand is received; detecting the kind of paper selected by a user; transmitting the image data to the laser scanning unit if the detected paper is a thick; and decreasing the amount of the light emitted from the laser scanning unit at a predetermined rate and performing the printing work.

In accordance with further another aspect of the present invention, the process contemplates storing image data to be printed at a memory if a print demand is received; detecting the kind of paper selected by a user; transmitting the image data to the laser scanning unit if the detected paper is a thick; and increasing a developing voltage applied to the developing machine to a predetermined voltage level and then performing the printing work. The predetermined voltage level is equal to or less than -250 volts.

BRIEF DESCRIPTION OF THE DRAWINGS

A more complete appreciation of this invention, and many of the attendant advantages thereof, will be readily apparent as the same becomes better understood by reference to the

following detailed description when considered in conjunction with the accompanying drawings in which like reference symbols indicate the same or similar components, wherein:

Fig. 1 schematically shows an image forming apparatus employing an electrophotographic developing technique;

Fig. 2 is a schematic block diagram of an image forming apparatus constructed according to the principles of the present invention;

Fig. 3 is a flow chart showing the first embodiment of a process for enhancing the image quality of the image forming apparatus according to the principles of the present invention;

Fig. 4 is a flow chart showing the second embodiment of a process for enhancing the image quality of the image forming apparatus according to the principles of the present invention; and

Fig. 5 is a flow chart showing the third embodiment of a process for enhancing the image quality of the image forming apparatus according to the principles of the present invention.

DETAILED DESCRIPTION OF THE INVENTION

Turning now to the drawings, Fig. 1 shows an image forming apparatus 100 such as a facsimile, a printer and a complex machine, employing an electrophotographic developing technique. Image forming apparatus 100 may be constructed with a pick-up roller 101, an electrification roller 102, a photosensitive drum 103, a transfer roller 104, a developing roller 105, a supply roller 106, a fixer 107 and a laser scanning unit ("LSU") 108 for printing certain image data onto a recording medium such as a cut sheet of paper that is withdrawn by pick-up roller 101 from the top side of a stack of cut sheets stored within paper cassette 109, and propelled along a path of conveyance 120

through apparatus 100. During the printing process, the electrification roller 102 uniformly electrifies the photosensitive substance coated on the external surface of the photosensitive drum 103 while rotating, and the light generated from LSU 108 forms an electrostatic latent image that is to be printed, on the electrified photosensitive drum 103. Then, there is a voltage difference between the supply roller 106 to which a higher supply voltage is applied and the developing roller 105 to which a lower voltage is applied. Therefore, negative charges move from the supply roller 106 to the developing roller 105. In this way, toner supplied to the developing roller 105 is coated on the electrostatic latent image formed on the exterior circumferential surface of photosensitive drum 104 to form a visible image. The high voltage of transfer roller 104 causes the visible image formed by the toner coating the surface of the photosensitive drum 103 to be transferred to the recording paper 109 delivered along path 120. After the transfer of the visible image onto the recording paper 109 is fixed on the recording paper 109 by the high temperature and high pressure of a heating roller 110 and the pressure exerted by pressing roller 111 mounted within fixer 107 to engage opposite sides of the recording media, thereby finishing the printing process and discharging a sheet of paper bearing toner particles that form a visible image. This sequence of supplying sheets of paper, developing, transfer and application of electrification voltages is continuously applied to the supply roller 106, the developing roller 105, the transfer roller 104 and the electrification roller 102, respectively until the printing process is completed for each job. The heating roller 110 in the fixer 107 is maintained in a turned-on state until the printing process has been completed.

I have noticed deficiencies in the pre-transfer system of image forming processes and apparatus. By way of example, if the user intends to form an image on a printable material that is

1 relatively thicker than the standard grade of xerographic paper such as an envelope, the toner coated
2 on the photosensitive drum is not transferred onto the paper and the remaining toner on the
3 photosensitive drum is transferred onto the next piece of printable material that passes along path
4 120, thereby causing a mis-transfer which is referred to as "ghost development", because the transfer
5 electric field can not transmit the thick paper. Moreover, when a thick envelope having a relatively
6 narrower width in comparison to a sheet of A4 or 8½" by 11" paper is used in a transfer system
7 using a conductive roller, in a state wherein a high voltage required for the transfer is applied to the
8 transfer roller, the conductive layer of the photosensitive drum is broken. This defect is frequently
9 referred to as a "pin hole", and occurs in the region (either on the right, the left, or possibly on both
10 sides of the sheet of the printable media) where the transfer roller and the photosensitive drum come
11 into direct contact with each other due to the absence of any intermediate printable media, thereby
12 causing fatal and unrepairable damage to the photosensitive exterior circumferential surface of drum
13 103.

14 Referring now to Fig. 2, a preferred embodiment of the present invention may be
15 implemented with an image forming apparatus 200 constructed with a central processing unit
16 ("CPU") 201 for controlling the image forming apparatus pursuant to a given operational program
17 as a whole. In particular, central processing unit 201 controls the function block in the image
18 forming apparatus in accordance with the particular kind of paper selected by a user of apparatus
19 200, thereby enhancing the image quality. In other words, central processing unit 201 attenuates,
20 or "faints" the image information derived from image data received from an external source such
21 a computer, a document scanner, or a telephone wire, and applies the image information to a laser

1 scanning unit ("LSU") 202 faintly by either reducing the number of pixels of light emitted from the
2 LSU 202, or by increasing the magnitude of the developing voltage when the user selects a thick
3 paper, thereby enhancing the transfer efficiency. Power convertor 203 receives the common
4 household line voltage, *i.e.*, either 110 volts or 220 volts, transforms the line voltage to a voltage
5 level required at each function block in the image forming apparatus, and then supplies the
6 transformed voltage to each function block under the control of central processing unit 201.

7 Developing voltage controller 204 controls the developing voltage applied to developing
8 roller 205 under the control of central processing unit 201. That is, developing voltage controller
9 204 increases the developing voltage level applied to the developing roller 205 from -300 volts to
10 -250 volts or more under the control of central processing unit 201, in accordance with the kind of
11 printable medium (*e.g.*, a cut sheet of xerographic grade paper) detected by central processing unit
12 201, in response to either a manual input by a user or a signal supplied by a sensor (*e.g.*, a sensor
13 deployed to detect passage of paper through a bypass tray or a paper thickness sensor) located along
14 the path 220 of conveyance through apparatus 200.

15 A memory 206 stores various operational programs for controlling image forming apparatus
16 200 through central processing unit 201 as well as the image data to be printed by image forming
17 apparatus 200. Laser scanning unit ("LSU") 202 scans signals of light corresponding to the image
18 data selected by the user to be printed onto the printable medium, in order to form electrostatic latent
19 images on the exterior circumferential surface of photosensitive drum 207. Electrification roller 208
20 electrifies the surface of the photosensitive drum 207 at a constant potential with a high
21 electrification voltage (-1.4 kilo-volts) drawn from power convertor 203. The supply roller 210

1 supplies the particles of toner drawn from the hopper of a toner container to developing roller 205
2 while rotating in contact with developing roller 205. A developing roller 205 applies the toner
3 supplied by supply roller 210 to the electrostatic latent image on the photosensitive drum 207 while
4 contacting the photosensitive drum at a constant pressure to form a visible image on the
5 photosensitive exterior circumferential surface of drum 207. Transfer roller 209 is electrified with
6 a high transfer voltage (+1.5 kilovolts) drawn from power convertor 203, and transfers the toner
7 coated onto the photosensitive exterior circumferential surface of drum 207 to the printable medium
8 delivered paper along path 220 while rotating in contact with the photosensitive drum 207 at a
9 constant pressure.

10 The operation of each of the several embodiments according to the practice of the principles
11 of the present invention including such an arrangement will now be described.

12 The First Embodiment

13 Fig. 3 shows in a flow chart, one of the processes for enhancing the image quality of the
14 image forming apparatus according to the practice of the instant principles, as a first embodiment
15 of the present invention. When a print work is selected by a user (step S1), central processing unit
16 201 stores within memory 206 image data transmitted from a computer or other external equipment
17 (step S2), and detects the kind of paper selected by the user (step S3). If the grade of paper selected
18 by the user at step S3 is determined to be a thicker stock of paper (step 4), central processing unit
19 201 performs an editing function to reduce the image data to be printed at a certain rate per each
20 pixel (step S5), and transmits the edited image data to the laser scanning unit 202 (step S6) and
21 performs the print work for the edited image data (step S7) by creating the image corresponding to

1 the image information onto the surface of the printable media. If the grade of paper selected at step
2 S3 is determined during step S4 to not be a thicker type of paper, central processing unit performs
3 a normal printing work (step S8). Then, central processing unit 201 determines whether or not the
4 printing work should be completed (step S9), and if additional printing is determined by step S9 to
5 be required for that job, central processing unit 201 proceeds to repeat all of the process after step
6 S5, or if step S9 determines that the print job has been completed, central processing unit 201
7 finishes the printing process.

8 Although there are various processes for the editing work, only two representative cases, that
9 are used in the printing work, are described herein. At a print mode, "Econo mode" and "Ret mode"
10 are present in various setting functions. The "Econo mode" is a process wherein, in order to
11 represent one pixel of the image data, the number of pixels of the light scanned is split into an
12 integer number N by laser scanning unit 202, and only certain areas among the number of pixels of
13 light split uniformly are emitted, thereby reducing the overall number of pixels to be illuminated.
14 This means that since the number of pixels of light emitted by light scanning unit 202 is less than
15 the number of pixels of light to be emitted for printing actual data during a normal printing mode,
16 the total amount of toner to be used during the printing is decreased and, therefore, the amount of
17 toner coated onto the photosensitive exterior circumferential surface of drum 207 from the
18 developing roller 205 is decreased. Accordingly, even though the transfer potential is low due to
19 the reduced amount of the toner coated onto the photosensitive drum 207, an adequate quantity of
20 toner to define the image to be printed can be transferred on the paper.

21 On the other hand, the "Ret mode" is a process wherein the print areas are split into a

1 plurality of small areas, and some of total pixels per each resolution in the respective split small
2 areas are removed. This mode is substantially similar to the "econo mode" in terms of both the
3 constitution and the effect.

4 The Second Embodiment

5 Fig. 4 shows a flow chart for a process of enhancing the image quality of printed images in
6 accordance with the second embodiment of the present invention. In Fig. 4, for the convenience of
7 explanation, illustrates some of the same steps as shown in Fig. 3. When a print work is selected
8 by a user (step S10), central processing unit 201 stores within memory 206 image data transmitted
9 from a computer or other external equipment (step S11), and detects the grade and type of paper
10 selected by the user (step S12). If the grade and type of paper selected by the user at step S12 is a
11 thicker paper (step 13), central processing unit transmits image data to be printed to the light
12 scanning unit 202 (step S14), and controls light scanning unit 202 to reduce the amount of the light
13 emitted from light scanning unit 202 onto the photosensitive exterior circumferential surface of
14 drum 103 at a certain rate (step S15), and then performs the print work with the reduced amount of
15 the light (step S16).

16 If the kind of paper selected at step S3 is not a thick paper, central processing unit performs
17 a normal printing work (step S17). Then, central processing unit 201 determines whether or not the
18 printing work is completed (step 18), and if not, proceeds all the steps after step S14, or if
19 completed, finishes the printing process. That is, since the amount of the light emitted from the light
20 scanning unit 202 is less than the actual amount of the light to be emitted for printing data, the
21 electrification potential of the photosensitive drum 207 is not sufficiently low. This means that the

1 engagement force of the toner coated on the surface of the photosensitive drum 207 is lowered.
2 Therefore, even though the transfer potential is low due to the low engagement force of the toner
3 transmitted from the developing roller 205 and coated on the photosensitive drum 207, sufficient
4 toner is transferred onto the sheet of paper conveyed along path 220.

5 **The Third Embodiment**

6 Fig. 5 shows a flow chart of a process for enhancing the image quality in accordance with
7 the third embodiment of the present invention. In Fig. 5, for the convenience of explanation, some
8 of the same steps employed in the processes of Figs. 3 and 4 are described. When a print work is
9 selected by a user during step S19, central processing unit 201 stores within memory 206 image data
10 transmitted from a computer, page or line scanner, telephone line, facsimile machine, or other
11 external equipment (step S20), and detects the weight, type, quality, grade, thickness or kind of
12 paper selected by the user during step S21. If the grade of paper selected by the user at step S21 is
13 determined during step S22 to be a thicker grade of paper stock, central processing unit transmits
14 image data to be printed to the laser scanning unit 202 (step S23), and controls the developing
15 voltage controller 204 to increase the developing voltage by a certain level (step S24), and in step
16 S25 performs the printing work with the toner transmitted to the photosensitive drum 207 according
17 to the increased developing voltage.

18 If the grade of paper selected at step S3 is determined during step S22 to not be a thicker
19 grade of paper, central processing unit 201 performs a normal printing job during step step S26.
20 Then, in step S27, central processing unit 201 determines whether or not the printing work is
21 completed, and if not, repeats all the steps after step S23, or if completed, stops the process.

1 When in the normal state, the developing voltage is maintained at about -300 V, the potential
2 of the surface of the photosensitive exterior circumferential surface of drum 207 illuminated by the
3 light scanned from the laser scanning unit 202 is maintained at about -50 volts. At that time, there
4 is generated a voltage difference of about -250 volts between the developing voltage of the
5 developing roller 205 and the surface potential of photosensitive drum 207 so that a large amount
6 of toner is transferred onto the photosensitive exterior circumferential surface of drum 207 from
7 developing roller 205. If central processing unit 201 determines during step S22 that a thicker grade
8 of paper has been selected by the user, when the developing voltage is increased below about -250
9 volts, if a voltage difference of about -200 volts or less is created between the developing voltage
10 of developing roller 205 and the surface potential of the photosensitive drum 207, the amount of the
11 toner transmitted to the photosensitive drum 207 from the developing roller 205 is reduced to less
12 than the amount of the toner transferred during normal printing jobs using a normal grade (*e.g.*, 20
13 pound cut sheets) of paper. Accordingly, although the transfer voltage is low due to the reduction
14 in the quantity of toner coated onto photosensitive drum 207, the quantity of toner that is transferred
15 is still sufficient to be transferred and form sharply defined images onto the paper selected by the
16 user.

17 The process for enhancing the image quality of the image forming apparatus in accordance
18 with the principles of the present invention endows image formation with notable advantages. That
19 is, in case that the image forming work is performed for a thicker stock of paper, by reducing the
20 number of pixels of the light emitted from laser scanning unit 202 and enabling a reduction in the
21 quantity of toner to be coated onto the photosensitive surface of drum 207, the transfer efficiency

1 and hence the image quality are enhanced. Moreover, by decreasing the amount of the light emitted
2 by laser scanning unit 202 and lowering the engagement force of the toner coated onto the
3 photosensitive surface of drum 207, the transfer efficiency and hence the image quality of the
4 resulting printed item are enhanced. In addition, by increasing the developing voltage by a certain
5 level and reducing the quantity of toner transferred from developing roller 205 and coated onto the
6 photosensitive surface of drum 207, the transfer efficiency and hence the image quality are
7 enhanced.

8 Although the invention has been shown and described with respect to the preferred
9 embodiments according to the present invention, it will be understood by those skilled in the art that
10 various changes and modifications may be made without departing from the spirit and scope of the
11 invention as defined in the following claims. Although specific components of the circuit are
12 exemplified herein, it is apparent to those skilled in the art that it is not intended to limit the present
13 invention and that the present invention may be practiced without the specific components. Further,
14 the detailed explanations on the related known functions or constitutions, which may render the
15 subject matter of the present invention vague or unclear, are omitted herein. Therefore, the present
16 invention should not be limited to the described embodiments and is defined by the appended claims
17 and the equivalent thereof.

WHAT IS CLAIMED IS:

1 1. A process for controlling a transfer voltage in an image forming apparatus, the image
2 forming apparatus comprising an electrification roller electrifying a surface of a photosensitive
3 drum, a laser scanning unit ("LSU") forming an electrostatic latent image on the surface of the
4 photosensitive drum, a developing machine making the electrostatic latent image visible, a transfer
5 roller transferring the image to a recording paper and a fixer fixing the image transferred to the
6 recording paper, the process comprising the steps of:

7 storing within a memory image data to be printed if a print demand is received;

8 detecting the kind of paper selected by a user;

9 editing by reducing the number of pixels of the image data at a certain rate if the detected
10 paper is a thick; and

11 transmitting the edited image data to the LSU and performing the printing work for the
12 edited image data.

1 2. The process according to claim 1, wherein the editing step is performed using Econo
2 mode in which the pixels of the light scanned are equally split into an integer number of pixels in
3 order to represent one pixel of the image data, and only a certain number of pixels among the
4 equally split pixels of the light are scanned.

1 3. The process according to claim 1, wherein the editing step is performed using Ret

mode in which the print area is split into a plurality of small areas, and some pixels among the total pixels for each resolution included in the respective small areas are removed.

4. A process for controlling a transfer voltage in an image forming apparatus, the image forming apparatus comprising a electrification roller electrifying a surface of a photosensitive drum, a laser scanning unit ("LSU") forming an electrostatic latent image on the surface of the photosensitive drum, a developing machine making the electrostatic latent image visible, a transfer roller transferring the image to a recording paper and a fixer fixing the image transferred to the recording paper, the process comprising the steps of:

- storing at a memory image data to be printed if a print demand is received;
- detecting the kind of paper selected by a user;
- transmitting the image data to the LSU if the detected paper is a thick; and
- decreasing the amount of the light emitted from the LSU at a predetermined rate and performing the printing work.

5. A process for controlling a transfer voltage in an image forming apparatus, the image forming apparatus comprising a electrification roller electrifying a surface of a photosensitive drum, a laser scanning unit ("LSU") forming an electrostatic latent image on the surface of the photosensitive drum, a developing machine making the electrostatic latent image visible, a transfer roller transferring the image to a recording paper and a fixer fixing the image transferred to the recording paper, the process comprising the steps of:

- storing image data to be printed at a memory if a print demand is received;

8 detecting the kind of paper selected by a user;
9 transmitting the image data to the LSU if the detected paper is a thick; and
10 increasing a developing voltage applied to the developing machine to a predetermined
11 voltage level and then performing the printing work.

1 6. A process according to claim 5, wherein the predetermined voltage level is equal to
2 or less than -250 V.

ABSTRACT

There is provided a process and an image formation apparatus for enhancing the image quality of an image forming apparatus such as a printer, a facsimile and a complex machine employing an electrophotographic technique, capable of obtain a good image quality even though the image is formed on a thick paper such as an envelope. The process comprises the steps of: storing image data to be printed at a memory if a print demand is received; detecting the kind of paper selected by a user; editing by reducing the number of pixels of the image data at a certain rate if the detected paper is a thick; and transmitting the edited image data to the LSU and performing the printing work for the edited image data.

Fig.1





Fig. 2



009070 256T960




Fig. 3

009020 45677950




Fig. 4




Fig. 5

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of:

Su-Jong JUNG

Serial No.: *to be assigned*

Examiner: *to be assigned*

Filed: 6 July 2000

Art Unit: *to be assigned*

For: METHOD FOR ENHANCING THE IMAGE QUALITY OF AN IMAGE
FORMING APPARATUS


TRANSMITTAL OF DECLARATION

Assistant Commissioner
for Patents
Washington, D.C. 20231

Sir:

This transmittal accompanies a Declaration without the signature by the inventor(s), for the above-captioned application. A Substitute Declaration with the inventor(s)'s signature will be filed upon receipt of the Serial No. for the above-captioned application.

Respectfully submitted,



Robert E. Bushnell,
Attorney for the Applicant
Registration No.: 27,774

Suite 300, 1522 "K" Street, N.W.
Washington, D.C. 20005
(202) 408-9040

Folio: P56147
Date: 07/06/00
I.D.: REB/na

AS A BELOW NAMED INVENTOR, I hereby declare that:

My residence, post office address and citizenship are as stated next to my name.

I believe that I am the original, first and sole (if only one name is listed below), or an original, first and joint inventor (if plural names are listed below), of the subject matter which is claimed and for which a patent is sought on the invention entitled:

TITLE: *METHOD FOR ENHANCING THE IMAGE QUALITY OF AN IMAGE FORMING APPARATUS*

the specification of which either is attached hereto or otherwise accompanies this Declaration, or:

☐ was filed in the U.S. Patent & Trademark Office on _____ and assigned Serial No. _____,

☐ and (if applicable) was amended on _____.

I hereby state that I have reviewed and understand the contents of the above-identified specification, including the claims, as amended by any amendment referred to above. I acknowledge the duty to disclose information which is material to patentability and to the examination of this application in accordance with Title 37 of the Code of Federal Regulations §1.56. I hereby claim foreign priority benefits under Title 35, U.S. Code §119(a)-(d) or §365(b) of any foreign application(s) for patent or inventor's certificate, or §365(a) of any PCT International application which designated at least one country other than the United States, or §119(e) of any United States provisional application(s), listed below and have also identified below any foreign applications for patent or inventor's certificate having a filing date before that of the application on which priority is claimed:

<u>27215/1999</u>	<u>KOREA</u>	<u>6 July 1999</u>	Priority Claimed:
(Application Number)	(Country)	(Day/Month/Year filed)	Yes [<input checked="" type="checkbox"/>] No [<input type="checkbox"/>]
_____	_____	_____	Yes [<input type="checkbox"/>] No [<input type="checkbox"/>]
(Application Number)	(Country)	(Day/Month/Year filed)	
_____	_____	_____	Yes [<input type="checkbox"/>] No [<input type="checkbox"/>]
(Application Number)	(Country)	(Day/Month/Year filed)	

I hereby claim the benefit under Title 35, U.S. Code, §120, of any United States application(s), or §365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application(s) in the manner provided by the first paragraph of Title 35, U.S. Code, §112, I acknowledge the duty to disclose information material to patentability as defined in Title 37, The Code of Federal Regulations, §1.56(a) which became available between the filing date of the prior application and the national or PCT international filing date of this application:

_____	_____	_____
(Application Serial No.)	(Filing Date)	(STATUS: patented, pending, abandoned)
_____	_____	_____
(Application Serial No.)	(Filing Date)	(STATUS: patented, pending, abandoned)

I hereby revoke all previously granted powers of attorney and appoint the following attorneys: Robert E. Bushnell, Reg. No. 27,774, Michael D. Parker, Reg. No. 34,973, and Darren R. Crew, Reg. No. 37,806, to prosecute this application and to transact all business in the U.S. Patent & Trademark Office connected therewith and with any divisional, continuation, continuation-in-part, reissue or re-examination application, with full power of appointment and with full power to substitute an associate attorney or agent, and to receive all patents which may issue thereon, and request that all correspondence be addressed to:

Robert E. Bushnell,

Attorney-at-Law

Suite 300, 1522 "K" Street, N.W.

Washington, D.C. 20005-1202

Payor No. 008439

Area Code: 202-408-9040

I HEREBY DECLARE that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under §1001 of Title 18 U.S. Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

FULL NAME OF FIRST OR SOLE INVENTOR: SU-JONG JUNG

Citizenship: Republic of Korea

Inventor's signature: _____

Date: _____

Residence & Post Office Address: 259 Kongdan-dong, Kumi-shi, Kyungsangbuk-do, Republic of Korea

FULL NAME OF SECOND JOINT INVENTOR: _____

Citizenship: _____

Inventor's signature: _____

Date: _____

Residence & Post Office Address: _____

FULL NAME OF THIRD JOINT INVENTOR: _____

Citizenship: _____

Inventor's signature: _____

Date: _____

Residence & Post Office Address: _____

FULL NAME OF FOURTH JOINT INVENTOR: _____

Citizenship: _____

Inventor's signature: _____

Date: _____

Residence & Post Office Address: _____

☐ Additional inventors are being named on separately numbered sheets attached hereto.